


C. M. HIGH, INC.



Since 1977



341 King Street, Myerstown, PA 17067
717-866-7544 www.cmhigh.com

Change Request

Owner : LEMOYNE BOROUGH
510 HERMAN AVE
LEMOYNE, PA 17043-1822

Number: 1
Date: 03/28/2024
Project: 23.1157 LEMOYNE-GLG SIGNAL MODS

Description: CR#1:NEW SIGNAL CONDUITS

We are pleased to offer the following specifications and pricing to make the following changes:

The following pricing reflects the costs associated with installing 1-3" Conduit in (3) different directional bores, price includes associated junction boxes, sidewalk repair and connection to existing mast arm foundations:

Materials:

3 Inch Conduit: 180 LF @ \$4.25
Junction Box, JB-27: 5 EA @ \$520.00
Concrete, Class A (Sidewalk Repair): 4 CY @ \$215.00
Signal Cable, 14 AWG, 3 Conductor: 1,600 LF @ \$0.50
Misc. Materials: 1 LS @ \$175.00
Material Amount: \$5,200.00 + 15% Markup
Subtotal: \$5,980.00

Equipment:

Foreman's Vehicle: 4.5 Days @ \$370.00
Trackhoe W/ Breaker: 8 hrs @ \$154.00
Dump Truck: 10 hrs @ \$58.00
Subtotal: \$3,477.00

Labor:

Electric Lineman: 90 hrs @ \$81.02
Operator, Highway Class 1: 18 hrs @ \$68.80
Laborer, Class 1: 60 hrs @ \$43.80
Laborer, Class 3: 50 hrs @ \$47.41
Carpenter: 10 hrs @ \$54.41
Labor Amount: \$14,072.80 + 15% Markup
Subtotal: \$16,183.72

Subcontractor:

Directional Boring: 3 Days @ \$4,400.00
Vac Truck: 12 hrs @ \$150.00
Core Drill: 9 EA @ \$70.00
Subcontractor Amount: \$15,630.00 + 5% Markup
Subtotal: \$16,411.50

The total amount to provide this work is **\$42,052.22**

Submitted By: JORDAN HARDING
PROJECT MANAGER

Approved by: _____

Date: _____